



Krishna Kanta Handiqui State Open University

Patgaon, Rani, Guwahati-781017

Advertisement No: KKHSOU/Advt./2018/07

File No :

Quotations are invited from Govt. Registered Contractor(s) for Construction of front portion of existing Road of Head Office, KKHSOU, Patgaon, Rani, as described below.

Sl. No	Description of the item(s)	Qty.	Unit	Rate to be offered (inclusive of all taxes)
1	Surface excavation not exceeding 50cm deep & averaging 30cm deep & getting out in soft/ Loose soil complete all as specified and directed.	35.50	Sqm	
2.	Returning, filling including spreading leveling, watering & well ramming in layers not exceeding 25cm complete all as specified and directed.	9.50	Cum	
3.	Removing excavated soil not exceeding 50mtr & depositing where directed at a level not exceeding 1.5mtr above the starting point complete all as specified and directed.	5.80	Cum	
4.	Mnl for 150mm thick (Compacted thickness) WBM, with coarse aggregate of grading to (60 to 40mm size) with lime stone, Sand stone, Flint or Quartzite, Spread, rolled & Consolidated to gradient and Camber required with 8 to 10 tone power roller complete all as specified and as directed.	6.50	Cum	
5.	Fixing only machine precast concrete interlocking paver block with grey cement and pigment any shape and size confirming to IS15658-2006 of 80mm thickness, M-40 grade complete all as specified and as directed.	45.50	Sqm	
6.	M/L for sand filling under floor or in foundation including watering and consolidation complete all as specified and directed.	3.05	Cum	
7.	M/L PCC 1:2:4 type B-1 (using 12.5 mm graded stone aggregate) as in edges complete all as specified and directed.	2.10	Cum	
8.	M/L Reinforced concrete pipe, 600 mm bore class NP2, laid and jointed complete with collars including set in cement mortar complete all as specified and directed.	5.00	R.M	

The quotation addressed to the Registrar should reach the University office on or before 19th February, 2018.

NB: *Total estimated price - Rs 70,639*

Sd/-

Date: 14/02/2018

Registrar