



Krishna Kanta Handiqui State Open University
Patgaon, Rani Gate, Guwahati-781017
Advertisement No: KKHSOU/Advt./2021/37
File No: KKHSOU/Construction/34/2010

Notice Inviting Tender

Krishna Kanta Handiqui State Open University, Guwahati invites sealed quotations from the Government registered contractors for painting works of M. S. Railing along with RCC post, cleaning and painting of Masonry Boulder Wall at the approach road to the main building of KKHSOU, Patgaon, Rani. They may quote their best rate (inclusive of all taxes) in the specified format given below. The quotation superscribe with "Painting of MS Railing along with post and Boulder Wall" and addressed to "The Registrar, KKHSOU, University's City Office, Resham Nagar, Khanapara, Guwahati-22 should reach the University office on or before 26/10/2021. Complete address with contact number of the bidder must be mentioned in the body of the sealed envelop." The date and place of the opening of tenders will be declared later on.

Date: 20.10.2021

Sd/-
Registrar

✂.....

To
The Registrar
Krishna Kanta Handiqui State Open University, Resham Nagar, Khanapara, Guwahati-22

Sub: Painting works of M. S. Railing along with RCC post, cleaning and painting of Masonry Boulder Wall.

Sir,

With reference to above, I would like to offer my best rate for the following items –

Sl. No.	Description of Item	Unit	Qty.	Rate	Amount
1.	(a) Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. Beam below steel railing 1x27.00x0.90 = 24.30M2 R.C.C. POST (B) 1X30X1.00X1.16 = 34.80 „ BEAM (B) 1x55.00x0.90 = 49.50 „ R.C.C.POST (C) 1x11x0.90x1.16 = 11.48 „ BEAM (C) 1x32.00x0.90 = 28.80 „ R.C.C. POST (F) 1x27x0.90x1.16 = 25.46 „ BEAM (F) 1X75.00X0.90 = 67.50 „ BOULDER WALL(A) 1x80.00x2.52 = 201.60 „ „ „ (D) 1x90.00x1.80 = 162.00 „ „ „ (E) 1x60.00x2.27 = 136.20 „ 741.64M2	M2	741.64		
2.	Applying priming coats with primer of approved brand and manufacture, having low VOC(Volatile Organic Compound) content. 3. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre. Qty as per Item no 1 = 741.64 M2	M2	741.64		

3.	Finishing walls with water proofing cement paint of required shade : 2. Old work (one or more coats @ 2.20 kg/10sqm) complete. Qty as Item no 1 = 741.64 M2	M2	741.64		
4.	With ready mixed red oxide zinc cromate primer of approved brand and manufacture on steel galvanized iron/steel works. 1. M.S.RAILING(B) 1x29x1.883 = 83.607 M2 2. „ „ (C) 1X11X4.012 = 44.132 „ 3. „ „ (F) 1x27x4.012 = 108.324 „ 236.063 M2	M2	236.063		
5.	Finishing with Epoxy paint(two or more coats) at all locations prepared and applied as per manufacture's specifications including appropriate priming coat, preparation of surface, etc. complete. 1. On steel work. Qty as Item no 4. = 236.063 M2	M2	236.036		

Date:

Signature:

Name of the Contractor:

Address:

Contact No:

E-mail:

Documents to be submitted along with the quotation:

1. Copy of valid registration certificate.
2. GST registration certificate
3. Income tax return document.
4. 2.5% of the quoted amount is required to be deposited as EMD along with tender document in the form of Demand Draft addressed to The Registrar, KKHSOU.